



1. Ground Preparation – Fill in deep contours, such as wheel ruts. To avoid punctures and tears, remove any objects from the ground, including rocks or other sharp debris.
2. Roll out **Ground Mat** protection, if available.
3. Unfold berm and position over ground mat.
4. Slide logs into sleeves, if not already assembled.
5. Install white plugs provided into drain assembly on berm.
6. Depending on weather conditions, determine if berm should be secured with sandbags or staked to the ground.

PRECAUTIONS

- All materials have limitations. Ensure the bottoms of skids are free of gravel, debris and any sharp edges prior to placing on berm.
- **DO NOT** drive on the yellow brackets as they will break.
- Avoid skidding the unit on the berm.

SAFETY

Consider slips, trips and falls while working on/in the berm. Fabric can be very slippery when wet or icy and yellow brackets may cause tripping hazards.

HDT Expeditionary Systems, Inc.

30500 Aurora Road, Suite 100, Solon, OH 44139 USA
P 800.969.8527 / 216.HDT.6111 / sales@hdtglobal.com

